BY ORDER OF THE COMMANDER
JOINT BASE MCGUIRE DIX
LAKEHURST

JOINT BASE MCGUIRE DIX LAKEHURST
INSTRUCTION 32-9008

16 SEPTEMBER 2015

Base Civil Engineer

FACILITY MANAGER PROGRAM

COMPLIANCE WITH THIS PUBLICATION IS MANDATORY

ACCESSIBILITY: Publications and forms are available for downloading or ordering on the e-Publishing website at **www.e-Publishing.af.mil.**

RELEASABILITY: There are no releasibility restrictions on this publication.

OPR: 87 CES/CEOS

Certified by: JBMDL/CC
(Col James C. Hodges)
Pages: 56

This instruction establishes policies, practices, and procedures for a comprehensive facility manager program for all organizations and agencies at Joint Base McGuire-Dix-Lakehurst (JBMDL). This instruction is applicable to all facility managers on JBMDL appointed to manage any facility that is included in Air Force real property records, regardless of occupying organization which includes, without limitation, all tenants and supported Components (as such term is defined in that certain Installation Support Memorandum of Agreement for JBMDL for implementing Base Realignment and Closure 2005 (JB Memo of Agreement)). It provides the Facility Manager (FM) with procedures to accomplish assigned duties. Further guidance can be found in AFPAM 32-1125 Volume 1, Chapter 11 and AFPAM 32-1004, Volume 3, Chapter 2.3.

Ensure that all records created as a result of processes prescribed in this publication are maintained in accordance with Air Force Manual (AFMAN) 33-363, *Management of Record*s, and disposed of in accordance with Air Force Records Information Management System (AFRIMS) Records Disposition Schedule (RDS) located at **https://www.my.af.mil/gcss-af61a/afrims/afrims/.** Refer recommended changes and questions about this publication to the Office of Primary Responsibility (OPR) using Air Force (AF) Form 847, *Recommendation for Change of Publication;* route AF Forms 847 from the field through the appropriate functional's chain of command.

CHAPTER 1—GENERAL INFORMATION **6**

1.1. Facility Manager (FM) Overview. 6

1.2. APPOINTMENT PROCEDURES. 6

1.3. FACILITY MANAGER ELIGIBILITY. 6

1.4. Mission Partner Support. 7

1.5. Facility Manager Training. 7

CHAPTER 2—FACILITY MANAGER'S PRIMARY RESPONSIBLITIES **8**

2.1. Facility Manager's Primary Responsibilities. 8

CHAPTER 3—GENERAL RESPONSIBLITIES **9**

3.1. Data Card. 9

3.2. Periodic Inspections. 9

3.3. SUBMITTING WORK REQUESTS. 9

3.4. Hands-On Maintenance of the Facility. 9

3.5. Emergency Preparation. 11

3.6. Base Disaster Recovery. 11

3.7. Assisting CE in Monitoring Custodial Service Contractors. 11

3.8. Continuity Binder. 11

CHAPTER 4—PROCEDURES FOR REQUESTING CE SUPPORT **13**

4.1. Contacting CE. 13

4.2. Requesting CE Services. 13

4.3. Work Classification. 13

4.4. Prioritizing CE Work Requests. 14

4.5. Explanation of Work Priority Terms. 14

4.6. Submitting AF Form 332 Requests via CE Tools Portal. 16

Table 4.1. Breakdown of CE Work Priorities. 17

Table 4.2. Priority Three Examples. 18

CHAPTER 5—KEY AND LOCK CONTROL POLICIES **19**

5.1. General. 19

5.2. Key Control and Key Records. 19

5.3. Avoiding Duplications. 20

5.4. Personnel Changes. 20

5.5. Controlled Area Locks. 20

5.6. Lost/Stolen Keys. 20
5.7. GSA Containers and Vaults. 20
5.8. Vacating a Facility. 20

CHAPTER 6—SPACE AND SYSTEMS FURNITURE MANAGEMENT 21

6.1. General. 21
6.2. Responsible Office. 21
6.3. Space Policy and Space Requests. 21
6.4. Renovating Existing Space. 22
6.5. Vacant Space/Vacating Facility. 22
6.6. Contractor Space. 22
6.7. Space Utilization Studies. 22
6.8. Systems Furniture. 23
6.9. Multi-Use Facilities. 23

CHAPTER 7—FACILITY SECURITY, AT/FPCON MEASURES, EM PROGRAM 24

7.1. General Overview/FM's Responsibility. 24
7.2. Facility Physical Security. 24
7.3. Antiterrorism (AT) Program. 24
7.4. Emergency Management Program. 25

CHAPTER 8—FIRE PREVENTION 27

8.1. General. 27
8.2. Daily Closing Inspection. 27
8.3. Monthly Fire Inspections. 27
8.4. Scheduled Fire Department Inspections. 27
8.5. Fire Extinguishers. 28

CHAPTER 9—BASE BEAUTFICATION AND LITTER CONTROL 29

9.1. Base Beautification Procedures. 29
9.2. CE Responsibilities. 29
9.3. FM Responsibilities. 29

CHAPTER 10—ENERGY & WATER CONSERVATION 31

10.1. General. 31
10.2. FM Responsibilities. 31
10.3. Contacting Energy Management. 31

CHAPTER 11—ENVIRONMENTAL GUIDANCE **32**
11.1. General. 32
11.2. Environmental Policy. 32
11.3. Environmental Management System. 32
11.4. Spills. 32
11.5. Recycling. 33
11.6. Hazardous Waste. 33
11.7. Pollution Prevention. 33
11.8. Air Pollution Control. 33
11.9. Storm Water Protection. 33
11.10. Environmental Impact Analysis. 33
11.11. Environmental Division Contact Information. 34
CHAPTER 12—REFUSE AND RECYCLING **35**
12.1. General. 35
12.2. FM Responsibilities. 35
12.3. Qualified Recycling Plan (QRP). 35
12.4. Recycling Center Locations. 35
12.5. Refuse/Solid Waste Disposal. 36
CHAPTER 13—SELF-HELP PROGRAM **37**
13.1. General. 37
13.2. Benefits to Organizations. 37
13.3. Self-Help Process. 37
13.4. Self-Help/Minor Maintenance Examples. 38
13.5. Material Support. 38
CHAPTER 14—SNOW & ICE REMOVAL PROCEDURES **39**
14.1. Removal of Snow and Ice. 39
14.2. Deicer Pick-up. 39
CHAPTER 15—MISCELLANEOUS PROVISIONS **40**
15.1. Base Signage. 40
15.2. Non-Fair Wear and Tear of Air Force Real Property. 40
15.3. Portable Space Heaters. 40
15.4. Public Access Defibrillation (PAD) Program. 41

Attachment 1—GLOSSARY OF REFERENCES AND ADDITIONAL INFORMATION 42

Attachment 2—SAMPLE FM APPOINTMENT MEMO 44

Attachment 3—FM CHECKLIST 45

Attachment 4—LOCK AND KEY CONTROL REGISTER 46

Attachment 5—KEY ISSUE LOG 47

Attachment 6—TEMPORARY ISSUE RECEIPT 48

Attachment 7—FACILITY MANAGER DATA CARD 49

Attachment 8—SAMPLE FACILITY ABUSE LETTER 50

Attachment 9—AF FORM 332 (EXAMPLE) 51

Attachment 10—JBMDL SPACE REQUEST FORM (EXAMPLE) 52

Chapter 1

GENERAL INFORMATION

1.1. Facility Manager (FM) Overview. The facilities at JBMDL that unit commanders or organizational leaders (Organizational Commanders) stage out of are an extension of the weapons systems such Organizational Commanders are charged with training, operating, and maintaining. Organizational Commanders need to view these facilities as weapons platforms and treat them with the same critical eye to ensure there is no disruption to our respective missions at JBMDL. The FM, who is appointed by Organizational Commanders, in cooperation with 87th Civil Engineer Squadron (CE) is the prime facilitator of this process. FMs, acting on behalf of the Organizational Commander and in cooperation with all occupants/users of a facility, are responsible for the care, custody, and protection of their assigned Air Force real property. FMs regularly work with CE personnel to coordinate facility support and routine maintenance. The FM is the primary point of interface between CE and the building occupants/tenant activities. Finally, the FM is charged with key control of their assigned facilities, knowing who operates in their assigned facilities, what their mission and particular needs are and establishing clear lines of communication between FM and occupants, among other things as more particularly set forth in this instruction.

1.2. Appointment Procedures.

1.2.1. Appointment and Appointment Letter. The Base Civil Engineer (BCE) has established the requirement and defined the responsibilities of the FM, including instructions for their assignment and relief. For each facility assigned to a base unit or organization, the organization's commander or civilian leader shall appoint, in writing, a primary and alternate FM. Base units or organizations will provide a completed memorandum (on the form provided on Attachment 2) that is signed by the respective Organization Commander or civilian leader to CE Real Property Office 87 CES/CEAO having an address at 5318 Delaware Avenue (Telephone: 609-562-4909/3690/3790 for Dix & McGuire or 732-323-2712/2601 for Lakehurst) for input into the Air Force Automated Civil Engineer System for all new/changes to FM appointments.

1.2.2. Delegation of FM Appointment Authority. Organization Commanders may delegate the authority to appoint FMs to the Officers, Non-Commissioned Officers (NCO), or civilians in their organizations with sufficient authority and knowledge to manage the actions of the unit FM designees. This delegation of authority will be indicated in an appointment letter similar in content to Attachment 2 (the routine appointment letter).

1.2.3. Change in Appointment Authority. It is the outgoing FM's responsibility to ensure a replacement is appointed. The FM appointment letter must be submitted to CE at least 30 days prior to any change. For continuity purposes, outgoing FMs should brief the new FMs on the details of their facility.

1.3. FACILITY MANAGER ELIGIBILITY. The Organization Commander will designate an officer, E-4 and above, or a civilian equivalent, as primary and alternate facility manager for each building assigned to that organization and advise the CE Real Property Office, in writing, of the assignment. Any changes in FM will be sent in writing to CE Real Property Office 10 days prior to the desired change date. Management support is required to keep facility manager

changes to a minimum, since frequent changes adversely affect the level of support that can be provided to the facility. Assigned managers should have at least one year retain-ability left on their assignment to be appointed. All FMs appointed shall have the ability to perform the assigned duties as the authorized representative of the Commander/civilian leader where practical, the primary duty assignment of the individual appointed as the FM should physically reside in the facility for which he/she is the FM (outlying facilities, such as navigational aids, communication facilities, ranges, training sites, test sites, and other similar facilities, are the exception).

1.3.1. Dix-Lakehurst Areas. Base units and organizations stationed in these areas may have problems meeting FM eligibility or retain-ability criteria. Units or organizations with these challenges should establish one central focal point for facility management for their organization to minimize FM selection criteria issues.

1.3.2. When a facility is occupied by more than one organization, each unit/organization will appoint a primary and alternate FM. Questions about occupied square footage should be directed to the CE Real Property Office, 87 CES/CEAO at 609-562-4909/3690/3790 (Dix & McGuire) or 732-323-2712/2601 (Lakehurst).

1.4. Mission Partner Support. CE provides support to tenant organizations and supported components (as such term is defined in the JB Memo of Agreement) in accordance with the Common Output Level Standards (COLS) and support agreements. These agreements inform the FM of support to be provided by CE and any potential limitations. The 87th Air Base Wing Business Office, is responsible for and holds these agreements and can be contacted for further information.

1.5. Facility Manager Training. The facility manager mandatory training course addresses FM responsibilities, as outlined in this instruction, and provides the FM with an introduction to CE work procedures, priorities, and methods. Facility manager training is required for each primary and alternate FM and should be completed within the first 30 days after appointment. Moreover, all existing FMs are required to attend annual refresher training. Training is provided by the area specific CE Customer Service sections and is offered on a monthly basis. The training schedule is distributed via the FM email-distribution list as is available upon request. Please contact your respective CE customer service section for the training schedule.

Chapter 2

FACILITY MANAGER'S PRIMARY RESPONSIBLITIES

2.1. Facility Manager's Primary Responsibilities. The Facility Manager Program is vital to the 87th CE's ability to maintain and repair JBMDL's facilities and infrastructure systems. The FM is the primary custodian for a given facility and the day-to-day point of contact between CE and the facility occupants. FMs serve as the liaison with CE on behalf of the commanders or civilian leaders who appointed them. FMs fill a crucial role in the facility maintenance and upkeep process by performing the following duties:

2.1.1. Identifying deficiencies of the facility. No one has a more intimate knowledge of the problems associated with a facility than the individuals who must live with those problems on a daily basis—the facility occupants—of which the FM is one.

2.1.2. Consolidating, managing and validating work requests required for the facility. While CE has the technical expertise to evaluate and find solutions to facility deficiencies, the FM has a firm grasp on how these deficiencies affect their organization's mission. The deficiency's effect on the customer's mission serves as the basis for work justification and prioritization. Further, by accepting facility requirements from one single point of contact (FM), this reduces duplicate work requests and ensures efficient use of CE manpower and resources.

2.1.3. Maintaining a professional appearance both inside and outside of the facility. This includes litter control enforcement, refuse collection points, and facility landscaping to be maintained within acceptable standards as defined in Chapter 9 of this instruction.

2.1.4. Ensuring facility occupants accomplish certain civil engineer tasks which are within their capability. This reduces the number of routine work requests, and allows CE to focus their limited resources (funds and personnel) on the most urgent and technical jobs.

2.1.5. Monitoring the quality and quantity of work associated with recurring service contracts, specifically custodial services and refuse removal. Although CE has Quality Assurance (QA) evaluators assigned to these contracts, inspections are conducted on random samples. Therefore, customer feedback is a significant means of monitoring QA. FMs are to assist CE in ensuring the overall performance of the contractors is within the acceptable parameters.

2.1.6. Maintaining positive control and force protection of facilities to include all keys. The FM is responsible for and controls all keys to buildings and facilities that they are appointed as the facility manager for. Additionally, the FM ensures facility occupants maintain a level of awareness and protection measures commensurate with the local threat conditions.

Chapter 3

GENERAL RESPONSIBLITIES

3.1. Data Card. FMs will post a completed Facility Data Card (Attachment 6) at the main ground floor entrances to the facility. The information should be readily visible to all occupants as they enter the facility.

3.2. Periodic Inspections. FMs are responsible for conducting periodic inspections of the assigned facility and its installed equipment, with particular attention to doors, windows, glass, lights, plumbing, heating, ventilation, and air conditioning equipment. Attachment 3 provides an example checklist for facility mangers to follow. Furthermore, these checklists are required to be maintained in the FM continuity binders and must be IAW section 3.8.

3.2.1. Dix Area. Several of the training facilities on the Dix area ranges have transient occupancy throughout the year. To limit the burden of routine periodic inspections, FMs charged with responsibility for these facilities will only be required to inspect them on a pre/post training basis or after long period of time in which the facilities are unoccupied.

3.3. SUBMITTING WORK REQUESTS.

3.3.1. FMs serve as the primary point of contact for CE services, maintenance, and repairs to their assigned facilities. FMs are responsible for consolidating, validating, submitting and tracking all work requests associated with their facilities. For details on requesting CE work see Chapter 4, *Procedures for Requesting CE Support*

NOTE: While occupants should route all routine work to the FM, **emergencies can and should be called into CE** immediately by anyone when they occur. Emergencies are considered to result in: complete mission stoppage, immediate threat to life, or damage to a facility. For further clarification see Section 4.3.1.

3.4. Hands-On Maintenance of the Facility. FMs play an active role in remedying minor maintenance deficiencies within their facilities to include:

3.4.1. Replacing burned out light bulbs (Either tube or incandescent bulbs).

3.4.1.1. McGuire-Lakehurst. All facility light bulbs are to be funded and purchased by FMs and their organizations. Lights bulbs located 10 feet in height or less shall be replaced by FMs. FMs will contact their area specific CE customer service sections for replacement of light bulbs greater than 10 feet.

3.4.1.2. Dix. All light bulbs regardless of location are replaced by the Dix Base Ops contractor. This is funded and covered under the contract. FMs may request these services via the Dix customer service section by calling 609-754-8723 and selecting Dix customer service.

3.4.2. Replacing stained, damaged, or missing ceiling tiles.

3.4.2.1. McGuire-Lakehurst. All ceiling tiles are to be funded and purchased by FMs and their organizations. Ceiling tiles located 10 feet in height or less shall be replaced by FMs. FMs will contact their area specific CE customer service sections for replacement of ceiling tiles greater than 10 feet.

3.4.2.2. Dix. All ceiling tiles regardless of height are replaced by the Dix Base Ops contractor. This is funded and covered under the contract. FMs may request these services via the Dix customer service section by calling 609-754-8723 and selecting Dix customer service.

3.4.3. Attempting to correct minor clogs of toilets, urinals, and sinks prior to calling CE.

3.4.3.1. McGuire-Lakehurst. Minor toilet, urinal, and sink clogs are to be remedied by FMs. Tools and supplies are available via the McGuire area Self Help store in Building 3104.

3.4.3.2. Dix. Minor toilet, urinal, and sink clogs are to be remedied by the Dix Base Ops contractor. This is funded and covered under the contract. FMs may request these services via the Dix customer service section by calling 609-754-8723 and selecting Dix customer service.

3.4.4. Fund, install, and maintain waterless urinal cartridges for all waterless urinals in facilities.

3.4.4.1. McGuire-Lakehurst. FMs must arrange for the funding, purchase, and installation of all waterless urinal cartridges at their organization's own expense. Due to the replacement and maintenance costs associated with urinal cartridges, unit organizations are responsible for this routine maintenance.

3.4.4.2. Lakehurst (NAVAIR Facilities). NAVAIR directly funds this requirement under the base custodial contract with CE and thus FMs for these facilities are not required to perform this routine maintenance.

3.4.4.3. Dix. All issues relating to the waterless urinal cartridges are remedied by the Dix Base Ops contractor. This requirement is funded and covered under the contract. FMs may request these services via the Dix customer service section by calling 609-754-8723 and selecting Dix customer service.

3.4.5. Labeling circuit breaker panels.

3.4.5.1. McGuire-Dix-Lakehurst. FMs are responsible for labeling circuit breaker panels if desired. Electrical surveys for labeling breakers can be accomplished by contract at user's expense.

3.4.6. Complying with cold weather procedures as required to include snow/ice removal and distribution of deicer around facilities. For delineation of FM responsibilities and specifics see Chapter 14.

3.4.7. Cleaning and correcting any small mold problems or water damage within capability (such as replacing ceiling tiles with minor water damage after ensuring CE has properly addressed the source of the leak).

3.4.7.1. It is imperative that FMs inspect and report moisture problems before mold and related microbial contamination become problematic. If mold is suspected, contact Bioenvironmental Engineering (BE) at 609 754-9066 for the comprehensive AF guidance and policy regarding mold prevention, surveillance and remediation. Since most cases of mold concerns are associated with water, the key to effective mold prevention requires

the FM to proactively identify and report to CE potential water leaks within assigned facilities. This includes:

3.4.7.2. Monitoring the facility for signs of water damage (e.g., spotted ceiling tiles, water marks near windows/doors or damp floors, etc)

3.4.7.3. Checking for signs of condensation and/or suspected mold growth around diffusers or HVAC vents

3.4.7.4. Verifying HVAC condensate drain pans are functioning properly

3.4.7.5. Confirming that the facility thermostat is maintained at the installations recommended temperature (Appendix C)

3.5. Emergency Preparation. FMs are responsible for emergency preparations for their facilities. This includes protecting the facility from flooding prior to hurricanes/significant storms by sandbagging low-lying entrances, mechanical room doors, basement windows, and other exterior openings adjacent to flood-prone areas. FMs are responsible for the filling, placement, and removal of sandbags prior to, during, and after emergency conditions.

3.6. Base Disaster Recovery. FMs will actively report any/all damages, utility outages or emergency conditions affecting their facilities during and/or after emergency conditions.

Note: FMs should report these conditions as soon as safely possible to the CE Unit Control Center (UCC) at 609-754-4415.

3.7. Assisting CE in Monitoring Custodial Service Contractors. If a facility receives contracted or other government custodial services, FMs are to conduct periodic inspections to ensure that all services are accomplished IAW custodial contract standards. For contracted services, the level of custodial service a facility receives is dictated by the mission performed within the facility. Each FM should be familiar with the terms of the contract, areas to be serviced, frequencies of service, and days that services are scheduled. The CE Quality Assurance monitor will brief FMs on the terms of the contract on an as needed basis. For questions concerning standards, the FM should contact their area specific Customer Service desk.

Note: FM's should not address concerns with the custodial contractor directly but rather report any unsatisfactory work to area specific CE customer service desk.

3.7.1. Dix Inmate Labor Program. Dix custodial responsibilities are aided by inmates from the Federal Corrections Institute (FCI). These individuals assist in the care and clean-up for several designated facilities across the Dix area of the installation. Complaints or concerns regarding the quality of inmate custodial service should be referred to the Dix area CE customer service desk.

3.7.1.1. Requests for Inmate Custodial Support. Requests for support on the Dix area of the installation should be channeled through the US Army, Inmate Labor Programs Coordinator at DSN: 562-6779.

3.8. Continuity Binder. FMs are required to maintain all records that provide a chronological history of the facility. Continuity binders must contain these documents/tabs at a minimum for each facility:

3.8.1. FM appointment memorandum (signed by unit CC)

3.8.2. FM training slides (provided during initial training)

3.8.3. FM Periodic Checklist (Attachment 3) (required to maintain the previous 1 year of inspections)

3.8.4. Safety and Fire Prevention documentation to include:

3.8.5. JBMDLI 32-2001, *Fire Emergency Services Program*

3.8.6. AFOSH Standard 91-56

3.8.7. AF Form 1487, *Fire Prevention Visit Report*

3.8.8. Fire drill record and other training forms (available in the JBMDL 32-2001)

3.8.9. Log and copies of requested CE work to include Direct Scheduled Work (DSW) & AF Form 332s.

3.8.10. Lock and Key Control Register and Key Issue Log. (Chapter 5 for guidance and Attachments 4, 5, 6 for example)

Chapter 4

PROCEDURES FOR REQUESTING CE SUPPORT

4.1. Contacting CE. CE has three separate and area-specific customer service desks which can be reached via the JBMDL customer service phone line at (609) 754-87CE or DSN 650-87CE. Standard duty hours are 0730-1615 Monday-Friday, however standby personnel are available outside those hours for emergency requests.

4.2. Requesting CE Services. All work requests, with the exception of emergencies, will be submitted by the FM to the respective CE customer service section. All occupants of the facility will channel CE work requirements through the FM for consolidation and shall not work independently of the FM to alter the facility in any manner. The following are the various ways for the FM to request CE services:

4.2.1. Calling customer service. The verbal method is used to request emergency or minor maintenance work. FM will receive a tracking number to place in their work order log. FMs can utilize the JBMDL customer service phone line as identified above to contact CE for these requests.

4.2.2. Electronically submitting. FMs also have the option of submitting requests for [**minor routine work]** via the following organizational boxes.

McGuire: 87ces.customerservice@us.af.mil

Dix: rachel.kelly.ctr@us.af.mil

Lakehurst: 87ces.lkh.cs@us.af.mil

Include the following information when submitting an electronic request:

Facility Number

Name (Rank if military)

Phone Number

Description of work to include the location of the problem within the building

4.2.3. Submitting AF Form 332. This form serves as a written request for construction work, alterations/renovations, modifications, self-help, routine maintenance and repair, and reimbursable work. See Section 4.6 on for details on submitting AF Form 332 requests via the CE Tools portal.

4.3. Work Classification. CE classifies work into three primary categories: Emergency (Unscheduled), Preventive Maintenance and Scheduled. This new system of classification moves away from the traditional model (emergency, urgent, and routine) and allows CE to apply scarce resources in a way that most effectively addresses life cycle management and mission priority. FM work requests will either be categorized as Emergency or Scheduled as Preventive Maintenance is accomplished by CE without request from the FM. The following are the descriptions of the various types of CE work:

Note: The new work classification model drives the CE work prioritization process as described in section 4.4.

4.3.1. Emergency. Emergency work represents immediate maintenance, safety, or mission risk. Emergencies are considered to result in complete mission stoppage, immediate threat to life, or damage to a facility. Emergency work can include, but is not limited to:

4.3.1.1. Utility line breaks.

4.3.1.2. Power outages or electrical shorts.

4.3.1.3. Complete loss of heat or cooling systems if the temperature extremes require operation during appropriate season.

4.3.1.4. Other facility deficiencies which would drastically affect the health and welfare of personnel (to include environmental compliance violations such as hazardous material releases or spills) or deficiencies, if not corrected, that will cause further damage, fire, or safety hazards which cannot wait until the next duty day

4.3.1.5. Fire or other disaster.

4.3.1.6. Natural gas leaks.

Structural damage creating hazards or affecting security compromise.

4.3.2. Preventive Maintenance consists of scheduled planned maintenance actions aimed at the prevention of breakdowns or failures of Real Property Installed Equipment (RPIE) and is accomplished by CE without request from the FM. It is designed to preserve and enhance equipment reliability by replacing worn components before they actually fail. Although, FMs do not necessarily play a role in facilitating and/or scheduling preventive maintenance, they may be asked to accommodate CE personnel in its accomplishment. Examples include: replacing HVAC filters, changing oil in motors, running emergency generators etc.

4.3.3. Scheduled. The majority of customer generated daily workload falls within this category. Scheduled work has multiple sub-categories and is classified primarily on the complexity of the requested work and man-hours required to complete. For detailed explanations and examples of this category please see the following section regarding the prioritization of CE work.

4.4. Prioritizing CE Work Requests. The basic premise behind identifying and prioritizing work is to ensure CE is assigning scarce resources to the right priorities. CE first considers safety and mission risks; however also responds to those areas where failure to act would lead to further degradation. For examples and a visual breakdown of the CE work priority system, see Table 4.1. CE work priorities are as follows.

4.4.1. Emergency

4.4.2. Preventive Maintenance

4.4.3. Scheduled Sustainment

4.4.4. Scheduled Enhancement

4.5. Explanation of Work Priority Terms. All work is prioritized based upon the above stated priorities.

4.5.1. Priority 1 is all emergency (unscheduled) work. Emergency work represents immediate maintenance, safety, or mission risk and will always be accomplished before

all other work. The goal is to eliminate the emergency hazard or perform a temporary fix until sufficient materials or resources are made available to complete a final repair. For examples of emergency requests, see paragraph 4.3.1. For further clarification and examples see **Table 4.1**.

4.5.2. Priority 2 is Preventive Maintenance (PM). PM is the first work accomplished after emergencies and is comprised of scheduled planned maintenance actions aimed at the prevention of breakdowns and failures. PM activities include equipment checks, partial or complete overhauls at specified periods, oil changes, lubrication, belts, filters etc. PM is accomplished without request from the FM but prioritized high since it is crucial to sustaining operations and ensuring effective equipment maintenance. For further clarification and examples see **Table 4.1**.

4.5.3. Priority 3 is scheduled sustainment work. As caretakers of the base infrastructure, CE is typically overwhelmed with requirements that exceed capacity. Further tools are needed to help triage this workload. Priority 3 work is divided into three sub-levels based on the type and description of the work and the maintenance risk of not performing the task as well as priority of the asset. Priority 3 work, regardless of sub-category, will always be completed prior to any Work Priority 4 enhancement work. All available resources will be applied to priority 1, priority 2 and then priority 3. Breakdown of priority 3 work is based on high, medium or low risk. Specifics examples of each are provided in Table 2 and the details are below:

4.5.3.1. Priority 3A High risk work. This sub-category priority is often associated with follow-up work to an Emergency (Work Priority 1) that was responded to and downgraded. Work that corrects life, health and safety deficiencies should also fall under 3A, i.e. RAC, FSD, etc. This identifies the task as having the potential for high risk to the asset and left unattended could become potentially worse. See Table 2 for examples.

4.5.3.2. Priority 3B Medium risk work. The priority is based on the scope of work, typically medium risk, and is responded to in an expedited manner to prevent failure. Failure to respond could lead to requirement becoming a 3A high risk. See Table 2 for examples.

4.5.3.3. Priority 3C Routine risk work. This is low priority and low risk maintenance. Low maintenance risk supports delays longer time periods to complete. See Table 4.2 for examples.

4.5.4. Priority 4 is classified as enhancement or discretionary work. Because this category does not sustain the installation's as-is state but instead seeks to enhance, the category is assigned the lowest scheduling priority. This category is the "nice to have" versus "need to have" type of work. As mentioned above, Priority 4 work is accomplished only if all priorities 1-3 have been scheduled/completed. All work in this category will be managed through the CE review committee, called the Work Request Review Board (WRRB). The WRRB will apply both asset management and the above stated prioritization scheme to determine if and when the work will be accomplished. Examples of this type of work include replacement of carpet or ceiling tiles, lighting upgrades, installation of electrical outlets, or repair of aesthetic additions, such as landscape lighting or minor construction associated with the facility. For further clarification and examples see Table 4.1.

4.6. Submitting AF Form 332 Requests via CE Tools Portal. CE utilizes the "CE Tools Portal" (an online based platform) for receiving, coordinating and approving AF Form 332 type requests.

4.6.1. Gaining access to CE Tools Portal. Upon appointment, FMs are responsible for applying for access to the CE Tools Portal platform by following the link below and selecting "Request Access." After CE customer service validates the FM status, rights to the CE Tools Portal are granted and FM can submit, monitor and track their requests for their assigned facilities. Details as to the submission, coordination process are provided during mandatory facility manager training.

CE Tools Portal Link:

https://a7ims.amc.af.mil/CEToolsPortal/pages/home.jsf

4.6.2. AF Form 332 Submission. The FM will prepare an electronic AF Form 332 through the CE Tools Portal for work involving any modification, minor construction, or significant level of effort (**other than minor routine maintenance**).

4.6.2.1. FMs should capture all requirements for a single facility on a single AF Form 332 submission. It is imperative that the FM provides as much information as possible focus specifically on **describing the requirement and its impact on the mission and not their solution to the requirement**.

4.6.2.2. Description of work requested should be supported as often as possible by sketches, plans, diagrams, photographs, specifications, drawings, and any other data or information which will provide a clear and concise description of the location and scope of the work requested. Include any referenced regulations and/or instructions with the request.

4.6.2.3. Justification must be complete, factual, and should indicate the urgency of the request, and include impact on the organization/mission if the work is not accomplished. The statement of requirements must be clear and concise so it can be fully understood by reviewing and approving authorities not having ready access to any reference documentation cited on the form. The AF Form 332 will include the required or desired date of completion. Keep in mind that approval and requested work completion expediency are based on your justification. References to regulations, manuals, and directives alone are not adequate.

4.6.3. Coordination process. After AF Form 332 requests are submitted, they are validated by customer service and then proceed to coordination with the required agencies. 332 Requests are required to be coordinated with the Fire Department, Environmental Division, Bioenvironmental Engineering, Security Forces, Communications, Ground Safety and potentially the CE community planner or Architectural Review Board prior to approval. If FMs require quicker coordination the FM has the option to hand-carry the AF Form 332 to the mandated coordinators prior to submitting to CE customer service.

4.6.4. Work Request Approval/Disapproval. After required coordination is obtained, the work request will then be forwarded to the WRRB and be either approved or disapproved depending on the nature and scope of the request. FMs are given advance notice of the WRRB date and time (typically via email) and are invited to attend and advocate their

particular request. Typically, WRRB are held on a weekly or bi-monthly basis. After approval is secured the WRRB chair will prioritize the work and determine the avenue of accomplishment. Work approval is based solely on the following criteria:

4.6.4.1. The request is not a duplicate of an existing requirement.

4.6.4.2. The request does not ask for work strictly prohibited by Air Force instruction, regulation, or policy, or other legally binding requirement.

4.6.4.3. The request requires more than 50 man hours of work. For requests which entail less than 50 man hours of work, the AF Form 332 will be canceled, and the request will be listed as a minor routine work request and accomplished by in-house CE forces. Note: For the Dix area of the installation, these requirements are slightly different: If requests are less than 32 man hours or $2,000.00 then the AF Form 332 request will be cancelled and accomplished as minor routine maintenance work.

Table 4.1. Breakdown of CE Work Priorities.

3B (Med)	Scheduled Sustainment Work (CM)	• Medium Mission/Equip Sustainment Risk • Tier 3 Assets/Equip • RAC 4 and 5 (Unabated)	• Tier 3 – Assets on CRP with MDI > 69 or CC focus items • Same concept as Pri 3 A work but at slightly lower category/mission dependency/maintenance risk • Not intended to substitute for projects not scoring well on the IPL	• HVAC at RAPCON feeding office space • Admin Facility • Base Gym • NCO Professional Development Center
3C (Low)	Scheduled Sustainment Work (CM)	• Low Mission/Equip Sustainment Risk • Tier 4 Assets/Equip	• Tier 4 – All other assets • Same concept as Pri 3 B work but at slightly lower category/mission dependency/maintenance risk • Not intended to substitute for projects not scoring well on the IPL	• Repair broken window in Club • Road/Parking signs NTSB driven reqmt etc • Warehouse space • Bowling alley • Auto hobby shop
4A	Scheduled Enhancement Work	• Work defined and prioritized by base • Work that does not contribute to sustain or to ensure continued mission operations	• Incorporates Wing/CC priorities specific to local mission/issues • Work can be accomplished via contract/Saber and "funded by others"	• Replacement of carpet or ceiling tiles • Lighting upgrades • Installation of electrical outlets
4B	All other Enhancement Work	• Work that does not contribute to sustain or to ensure continued mission operations	• Work can be accomplished via contract/Saber and "funded by others" • Not intended to substitute for projects not scoring well on the IPL	• Irrigation systems • Parking Signs • Static Displays • Building Signage • Air Shows • Ornamental Landscaping • Marquees

Table 4.2. Priority Three Examples.

Priority 3A – High Risk	Priority 3B – Medium Risk	Priority 3C – Low Risk
No heat/cool in alert facility crew rest quarters Aircraft paint booth exhaust fan #2 needs belt Steam clipper inoperative in dining facility HVAC unit is showing inoperative air flow - required for equipment cooling Repair outdoor condenser fan – required for equipment cooling All bathrooms backed up Roll up doors, crush hazard is inoperative Repair clogged toilet - only one restroom in facility Repair turnstile for secure facility Repair inoperative base perimeter/sensitive area vehicle gate Breaker keeps tripping to mission critical equipment Generator panel is flashing "battery trouble" No hot water in bldg (medical or food preparation facility only) Multiple roof leaks throughout the facility - damaging office equipment/finishes	No heat/cool in entire facility during extreme environmental conditions or secure area w/ no other ventilation method Adjust heat/cool at Dining Facility - caller stated that facility was too hot Several rooms with no power coming out of the power outlets Repair emergency lighting at HVAC plant Conference room lighting and emergency circuit inoperative Water backed up in handicap shower Fire door will not close properly, binds in door jam Gate was blown down – medium priority security concern Multiple roof leaks throughout aircraft hangar Repair roof damage No hot water in dorm room Repair/replace several ballasts in room	Repair concrete base to tanks Attached lock to fire hydrant Repair drywall Leaking faucet in kitchen area Repair inoperative vehicle gate to compound area – low security concern No hot water in bldg (non-medical/food preparation facility) Breaker to outlet keeps tripping Conference room lighting and emergency circuit inoperative No heat/cool in entire facility – no mission/safety concern No power coming out of the power outlets in several rooms Repair/replace one ballast in room Break in the fire wall in the electrical closet Sink water sensor inoperative

Chapter 5

KEY AND LOCK CONTROL POLICIES

5.1. General. FMs are accountable for the security of all keys servicing their facilities.

5.2. Key Control and Key Records. All FMs are responsible for establishing and maintaining positive key control for the facilities that are assigned to them. Specifically, FMs are responsible for taking the following actions:

5.2.1. Taking receipt of and accepting responsibility for all keys to all facilities assigned to them, to include the redistribution of keys to other occupants or users as directed by their Organizational Commander.

5.2.2. Establishing and maintaining a key control register and key control log on an AF IMT 2427 (*Lock and Key Control Register*) (Attachment 3), AF IMT 2432 (Key Issue Log) (Attachment 4) and AF IMT 1297 (Temporary Issue Receipt) (Attachment 5) or a locally produced key log which shall be used to account for all keys issued for each facility and which is required to be in the continuity binder as stipulated in section 3.8.

5.2.3. Requesting duplicate keys or lock change requests on an AF IMT 332.

5.2.3.1. CE Customer Service will only issue and accept AF IMT 332 requests for keys from the primary or alternate facility manager. Requests for more than five keys at a time or repeated requests for additional keys in the same facility will be closely scrutinized by CE to determine the cause. If CE determines the keys are required due to a lack of key control or unit negligence, the user will be responsible for paying for the additional keys.

5.2.3.2. Additionally, lock replacement requests will be closely scrutinized by CE to determine the cause. If new locks are requested due to lost keys or unit negligence, the user will be responsible for funding the lock replacement requirement and all associated keys.

5.2.4. Signing for, securing, and maintaining control of facility master keys. Only two master keys shall be issued per facility. These keys will be held and maintained by the Organization Commander and FM. If more than two master keys are required, a letter of justification signed by the Organization Commander must accompany the AF IMT 332 stating why additional master keys are required. When FM or Organization Commanders leave, arrangements must be made with the by the new FM or Organization Commander to transfer responsibility of the “master” key(s) from one individual to another. If a master key is lost, the individual/unit that signed for the key will be responsible for funding the rekeying of all locks affected. Requests for require master keys will not be processed without the concurrence of the Organizational Commander and approval by the (BCE) via an AF IMT 332.

5.2.5. Ensuring transfer of facilities from one FM to another FM includes a transfer of all applicable keys. Organization Commanders shall be responsible for ensuring that keys are properly transferred from one FM to another FM within the same unit. However, if a unit vacates all or a portion of a building, the FM shall be responsible for collecting, labeling and turning in all keys to CE’s Real Property Office for the space being vacated. Under no

circumstances shall a FM transfer or reissue keys to another unit without first confirming with the CE Real Property Office that the other unit has been approved to use the space by the Real Estate Working Group (REWG) and Facilities Utilization Board (FUB or FB) or Installation Commander.

5.3. Avoiding Duplications. FMs shall establish security procedures to make sure there is no duplication of keys without personal approval from the FM.

5.4. Personnel Changes. FMs are required to repossess all keys from personnel going through a Permanent Change of Station (PCS), as well as, those personnel who are departing due to discharge or termination of employment. Keys issued to personnel going on extended leave or on a temporary duty assignment for over 30 days should be held for safekeeping.

5.5. Controlled Area Locks. FMs must appropriately monitor requests for Mechanical Electrical Combined Locks (MECL) and Manual Push Button Lock Systems for controlled areas. These lock systems have a high replacement and long term maintenance cost while doing little for security. Any future request for either system will require written justification routed through organizational FMs and commanders or civilian leaders. Justifications must include AFI or OI references and must express mission impact.

Note: These requests must be initiated via the AF Form 332. CE shop personnel will continue to replace these devices through attrition. However, any desire to keep the existing locking system will be the FM organization's own expense and combination changes will be performed by the using organization. As a device fails, it will be replaced by a High Security Cylinder Lock set unless a higher security lock set is justified. Customers are not authorized to privately purchase MECL's and have them installed by an outside locksmith.

5.6. Lost/Stolen Keys. Any person losing keys must notify their immediate supervisor and FM immediately to ensure against compromising facility security. The FM will notify CE Customer Service and follow up by submitting an AF Form 332 for installation of new locks and the issuing of new keys. Additionally, at the discretion of the Organizational Commander, a report of survey may be required in the case of a misplaced key. Once FM receives notice of lost key(s), they will:

5.6.1. Have all affected cores replaced, if deemed necessary by submitting an AF Form 332.

5.6.2. Reissue key(s) to individual.

5.6.3. Notify organization involved that the cost for rekeying an area due to lost/stolen keys or duplicated keys is their responsibility. A letter to the 87 ABW Funds Management Office requesting costs be taken out of the organization's funds will be initiated.

5.7. GSA Containers and Vaults. Limited safe and vault repair is done for organizations on the installation, but it is dependent upon scope. Requests must be submitted on an AF Form 332 signed by the FM. Note: If there is an emergency need, organization's FM can contact CE customer service to obtain potential base locksmith support. If a contracted locksmith service is required, it is the responsibility of the requesting organization to fund and coordinate.

5.8. Vacating a Facility. When vacating a facility for disposal or other reasons, ensure that the facility is left in a clean and orderly condition. The FM duties are formally terminated when the facility is completely vacated by the using organization, accepted by the CE Real Property Office as vacant, and the keys are accounted for and turned in to the CE Real Property Office.

Chapter 6

SPACE AND SYSTEMS FURNITURE MANAGEMENT

6.1. General. Since joint basing in 2009, JBMDL has experienced significant changes and a great blending of military cultural processes in the way space requirements and space requests are handled. It is important that CE maintain control over all Air Force owned facilities to ensure there is adequate space to accomplish all mission requirements and to properly account in the Air Force real property records accurate category codes and customer codes assigned to all facilities at JBMDL. The three primary goals of JBMDL space management are to reduce by 20 percent the amount of physical plant that requires funds by year 2020 pursuant to Air Force policy, efficiently utilize facility space to conserve energy, reduce costs, facilitate the demolition of surplus facilities and improve the accuracy of the real property records and maintain compliance with Air Force facility utilization standards.

6.2. Responsible Office. The CE Real Property Office, 87 CES/CEAOR, is the primary installation contact and responsible office for all space requests, temporary or permanent, regardless of area, or occupying organization. The Air Force takes space management seriously and has required that all space requests for use of any facility located on JBMDL be coordinated through the responsible office and approved per JBMDL policies, including without limitation this instruction.

6.3. Space Policy and Space Requests. All organizations, units, tenants, new programs, and users who require any facility space on JBMDL shall request space through the CE Real Property Office, 87 CES/CEAOR. The space request shall be submitted to the CE Real Property Office on the space request form which is set forth on Attachment 9 and shall include a completed DD1450 and DD1450-1. All space requests shall detail the requirements that mandate facility space. Space shall be allocated based on requirements and compatibility with the Installation Master Plan, not the availability of specific facilities. Additional documentation, such as organizational charts, floor plans, mission requirements and staffing requirements, should be included with the request to further justify and clarify requirements. All requests for space will be reviewed to validate whether the requested space is authorized by applicable space regulation. CE Real Property Office shall attempt to satisfy mission requirements with resources available at JBMDL. Organizations requesting additional space must first demonstrate that every reasonable effort has been made to satisfy their space allocation needs within their existing assigned assets. All facilities at JBMDL that are Air Force real property assets are subject to periodic utilization reviews and agency audits regardless of assigned organization. Subletting of assigned space to another organization without REWG and FB approval is expressly not permitted. In addition, all space allocations associated with new programs or missions, beddowns, support agreements or non-DoD contracts, shall first be worked with 87 ABW/BO. Space assigned prior to full acceptance of the program shall be contingent upon all proper paperwork and approvals from the wing and/or AMC formally accepting the program before the program can begin occupying space.

6.3.1. Verification. The CE Real Property Office will ensure the space request is authorized IAW AFMAN32-1084, *Facility Requirements*, or the respective individual service's equivalent space regulations. This will empower the search and selection of a suitable location, if available at JBMDL.

6.3.2. Search. The CE Real Property Office will review each space request and evaluate available assets in the Air Force real property inventory in order to attempt to locate the desired authorized amount of space based on space criteria specified by governing regulations

6.3.3. Site Walkthrough and Approval. CE Real Property will contact the requestor for a walkthrough of the site. If satisfactory, the request will be submitted to the REWG for initial approval with follow on approval and signature by the 87 ABW/CC at the Installation FB.

6.4. Renovating Existing Space. FMs are required to coordinate and receive approval via the AF Form 332 process prior to completing any renovation or alternation of facility space. CE has experienced several instances of unauthorized modification or removal of systems furniture workstations as well as the construction of private offices and training rooms without proper coordination. These actions have resulted in a net loss to our administrative workspace and often cause potential building infrastructure concerns. In addition, unauthorized renovations of existing space may result in a category code change which must be first reviewed by CE and ultimately approved by the REWG and FB.

6.5. Vacant Space/Vacating Facility. Organizations vacating rooms or facilities shall notify the CE Real Property Office at least 30 days in advance of a move. A final walk-through must be scheduled with the CE Real Property Office to ensure the vacated facilities are cleaned and emptied of all furnishings, equipment and trash. This will allow the CE Real Property Office to validate clearance of the facility. FMs shall be responsible for making appropriate disposal arrangements for the disposal of unwanted furnishings and non-real property. Keys to the vacated areas shall be accounted for and returned by the FM to the CE Real Property Office. If an organization moving into vacated space requests items be left behind, arrangements in the form of a Memorandum for Record between the shall be in place between the two organizations before the organization moving out can be released from its obligations. The FM's responsibility will be formally terminated by inspection by CE Real Property Office when the property is vacated by the using organization and CE Real Property has cleared the organization from the facility.

Note: The departing or vacating occupant must never grant permission to use space in any facility, either expressly or implied, to any co-occupant or interested occupant of the facility being vacated. All keys shall be turned in to the CE Real Property Office and the FM will be cleared IAW chapter 5 of this instruction.

6.6. Contractor Space. Prior to committing space to contractors, each organization must submit a written space request to CE Real Property Office for review and approval by the REWG and FB or Installation Commander. Although, space may be readily available, requests must receive CE Real Property Office in order to prevent committing space to contractors that may be required for mission requirements at JBMDL.

6.7. Space Utilization Studies. Organizations can request space utilization studies through CE Real Property Office when they do not know proper procedure to organize respective service/organizational space requirements. For this type of request, FMs should submit a space request and ensure coordination through CE Real Property Office.

6.7.1. Supported Components at JBMDL. Per the terms of the JB Memo of Agreement, certain supported Components (as such term is defined in the JB Memo of Agreement,

including, without limitation, United States Army and United States Navy) retained the right to manage certain "mission support" facilities which are deemed critical to their respective mission. While all facilities on JBMDL are part of Air Force real property records for which the Air Force is accountable for, the Air Force does not directly control these "mission support" facilities defined in the JB Memo of Agreement. Notwithstanding the foregoing, FMs for all "mission support" facilities at JBMDL and the FMs that manage these facilities are obligated to notify the CE Real Property Office of any changes in use (such as category code changes) and changes in occupants/customers of the facility so that proper Air Force approvals may be obtained in advance, if required, and Air Force real property records can be updated and maintained to reflect accurate data.

6.8. Systems Furniture. FMs are required to submit and receive approval via an AF Form 332 prior to purchasing new systems furniture or modifying installed systems furniture.

Note: System furniture is not considered Real Property Installed Equipment (RPIE) and thus CE is not responsible for the maintenance or repair of such systems. Further, CE is not responsible for electrical connections to systems furniture procured without prior CE approval.

6.9. Multi-Use Facilities. All organization FMs must be involved in space management decisions within multi-use facilities.

Chapter 7

FACILITY SECURITY, AT/FPCON MEASURES, EM PROGRAM

7.1. General Overview/FM's Responsibility. FMs are responsible for the physical security of their assigned facilities and play an active role in ensuring the safeguard of the facility occupants during emergency situations. Specifically, the facility manager fulfills the following three functions:

7.1.1. Ensures the physical security of their assigned facilities

7.1.2. Initiates and assures implementation of antiterrorism and force protection measures

7.1.3. Acts as the primary facilitator of the facility emergency management program

7.2. Facility Physical Security. The FM shall establish procedures according to mission needs or requirements for opening and closing the facility, including security measures to be observed during normal and after duty hours. This includes establishing standard procedures for ensuring the facility is secure from illegal entry at all times, double checking all doors and windows when departing, and regularly certifying that all locks are in good working order.

7.2.1. Procedures for Unsecured Facility. Security Forces Law Enforcement Patrols conduct regular security checks on base facilities. If the facility is required to be secured after duty hours and is found open during a check by the 87th Security Forces Squadron (87 SFS), the FM must be present prior to re-securing the facility. An AF Form 1168, *Statement of Suspect/Witness/Complainant*, will be sent to the organization's leader for action. If there are questions concerning facility security, contact the Security Forces Crime Prevention Section, the Resources Protection Section, or the Base Defense Operations Center (BDOC) at 754-2001.

7.3. Antiterrorism (AT) Program. The FM is an integral part of the AT program, and must develop and maintain a solid working relationship with the unit/agency AT Officer (ATO) or representative (ATR). It is the FM's responsibility to be familiar with the JB MDL Force Protection Condition (FPCON) CONOPS and corresponding FPCON checklist. The FM must ensure that all required measures are met during FPCON changes and increased security actions. The FPCON checklist is maintained, updated and distributed by the 87 ABW/ATO to the unit/agency ATO/ATR.

7.3.1. Reporting Suspicious Activity. If FMs suspect suspicious activity in or around their facility, they are to report this immediately to the Joint Base Police at: (609) 754-COPS (2677). Examples include:

7.3.1.1. Unknown individuals watching facilities, taking notes, or photographs

7.3.1.2. Unknown individuals asking suspicious questions about the base, its missions or people

7.3.1.3. Unknown objects found in or around facilities

7.3.1.4. Building Standoff. The FPCON checklist contains measures for clearing a 25-meter standoff area around facilities, and FMs need to have the resources and capability

to establish and enforce the standoff. Unit/agency ATOs/ATRs will advise FMs on meeting this requirement, as needed.

7.4. Emergency Management Program. The FM is a vital part of a comprehensive EM program. There are two components of the EM program that are of particular interest to the FM and must be thoroughly executable by all occupants. They are Evacuation and Shelter In-Place (SIP) activities. The FM must be knowledgeable of the facility Evacuation and SIP procedures as he/she is responsible for executing each facility's SIP and evacuation operation.

7.4.1. Evacuation. Evacuation is used to move personnel away from danger during emergency situations. Evacuation procedures and escape route assignments must be developed for each facility so employees understand who is authorized to order an evacuation, under what conditions an evacuation would be necessary, how to evacuate, and what routes to take.

7.4.1.1. Utilizing the facility evacuation plan, select primary and alternate evacuation locations. Educate all facility occupants on evacuation locations and proper procedures to follow during an event. These pre-identified locations will be used in the event of an evacuation order due to an emergency such as fire or a bomb threat. Evacuation locations should be at least 500 feet from your facility, preferably in opposite directions to account for wind direction (try to stay upwind of a hazard area).

7.4.1.2. If possible, select another building as your evacuation rally point. This will ensure all personnel are out of the elements and, in the event of an Improvised Explosive Device or bomb, offer more protection than simply moving to a parking lot. Ensure you coordinate with the proposed evacuation location facility manager prior to an event occurring.

7.4.1.3. Develop a facility specific checklist for each personnel to follow. Include in your checklist a step to "**SEARCH FOR ANY SECONDARY DEVICES OR SUSPICIOUS ITEMS**". If anything is found or something appears to be out of the ordinary at your primary evacuation point, then have all personnel move to the secondary evacuation point.

7.4.1.4. Do not transmit within 500 feet of the suspicious device with radios, cell phones, or any other type of communication device. Do not touch, handle, or examine the device. Call 9-1-1 once clear of the device. If using a cell phone to call 9-1-1, your call will go to Burlington County 9-1-1 center. Identify your location as being on JBMDL and they will transfer you back to JBMDL emergency services.

7.4.1.5. Treat injured within capabilities and conduct roll call once personnel have assembled at the location. Notify your control center of accountability status (include those not from your organization), new location, event details as specific as possible and new contact number/method. Follow the directions of response personnel.

7.4.2. **Shelter in Place**. Shelter in Place (SIP) is a process for taking immediate shelter in a location by sealing an area from outside air contaminates. The FM and unit Emergency Preparedness Liaison are key to a successful SIP program. Emergency Management personnel will assist in SIP room(s) identification, occupant load numbers, and air calculations. In addition, every facility has been provided a SIP kit(s) with requisite material initially provided. The restocking of SIP kit materials is a unit responsibility.

7.4.2.1. Conduct SIP exercises semiannually at a minimum. If needed, conduct monthly until facility personnel are well trained on the procedures. Highly recommend cutting and marking plastic before an event or training drill to aid in quickly covering vents and other openings. After every training event, do an inspection of the kit(s) to ensure all required items are accounted for and restock as necessary. Keep in mind that all SIP kit items are real world and if any kit items are lost, stolen, or otherwise unusable the unit is responsible to reconstitute the SIP kit.

7.4.2.2. When directed to SIP, inform all personnel assigned to the facility by PA system, runner, etc. Close and lock office windows, close and lock doors, and post SIP warning signs on exterior doors on the way to the SIP room(s). If able/authorized, turn off ventilation system. If not able to turn off ventilation system place plastic over air vents and affix securely with duct tape if safe to do so. Place plastic over SIP room windows/openings (if any) and seal edges with long strips of duct tape. Ensure tape securely overlaps all edges of the plastic. Lock door to SIP room and seal door edges with long strips of duct tape.

7.4.2.3. Once the SIP room is secure, tune into JBMDL radio (AM 1650), watch for desktop alert notifications, and check email for further directions. Take accountability of personnel in SIP room, make contact with your unit control center and report names and condition of all shelter occupants. For planning purposes the expected time to SIP should be between two to three hours. When the "All Clear" is announced, immediately remove duct tape/plastic from doors, windows and vents. Turn on the ventilation system (if disabled) and open all windows and exterior doors to receive fresh air.

7.4.3. Evacuation and Shelter in Place Guide. Refer to the JBMDL Evacuation and Shelter in Place Guide for further information. A copy may be obtained from you organization's Emergency Preparedness Liaison (EPL) or requested via email by sending to: **87CESCEXTraining@us.af.mil**

Chapter 8

FIRE PREVENTION

8.1. General. FMs have specific duties and responsibilities in maintaining fire safety conditions in their assigned facility. As stipulated in section 3.7, the FM should maintain a copy of and be familiar with JBMDL Instruction 32-2001, *The Fire Protection Operations and Prevention Program*. The following are the facility manager's specific responsibilities:

8.1.1. Ensure that all assigned facilities are numbered and this number is visible from the road.

8.1.2. Correct fire hazards and deficiencies in a prompt manner. If necessary, ask the fire inspector for advice.

Note: Fire hazards are defined as an existing condition or situation which, if not corrected, could result in undesired ignition and subsequent fire or rapid spread of fire causing personal injury, loss of life, loss of materials and the destruction of property. All fire hazards must be corrected immediately.

8.1.3. Ensure facility occupants understand the actions necessary in case of fire. These include:

8.1.3.1. Activating the fire facility fire alarm. All automatic fire alarms must be treated as a fire unless otherwise determined by the Fire Department.

8.1.3.2. Evacuate the facility or area immediately.

8.1.3.3. Notify the Fire Department by dialing 9-1-1.

8.1.3.4. Utilize portable firefighting equipment to extinguish a fire if discovered in its early stages.

8.1.3.5. Meet the fire vehicles and direct the firefighters to the fire.

8.2. Daily Closing Inspection. Conduct a closing inspection at the end of each workday or activity period, to ensure closing items listed in JBMDLI 32-2001**,** Chapter 11 are adhered to.

8.3. Monthly Fire Inspections. Perform monthly fire inspections and accomplish follow up on all discrepancies and irregularities noted during fire and safety inspections to ensure corrective action.

8.4. Scheduled Fire Department Inspections.

8.4.1. The primary or alternate FM will accompany the fire inspector during scheduled inspections and initiate corrective action for fire hazards noted during the inspection.

8.4.2. After these inspections, the fire inspectors may note fire hazards and deficiencies on AF Form 1487, *Fire Prevention Visit Report***,** and provide instructions for required corrective actions. If this information is not received during the inspection or in a follow up report, contact the base Fire Department for assistance.

8.4.3. During inspections, fire prevention inspectors pay particular attention to:

8.4.3.1. The occupant's knowledge of fire reporting, evacuation, and use of fire extinguishers.

8.4.3.2. Ensure evacuation plans are posted in a highly visible area of the facility.

8.4.3.3. The adequacy of safe practices to prevent fires.

8.4.3.4. The control of smoking and the proper disposal of smoking materials.

8.4.3.5. The condition of electrical equipment and connections, to include those associated with systems furniture.

8.4.3.6. The adequacy, condition, and accessibility of fire exits and fire doors.

8.4.3.7. The adequacy, condition, location, and accessibility of portable fire extinguishers.

8.5. Fire Extinguishers. FMs and user organizations must budget for the purchase and maintenance of such fire extinguishers. In addition, if facility is equipped with a generator, ensure a dry chemical fire extinguisher is located in the immediate area.

Chapter 9

BASE BEAUTFICATION AND LITTER CONTROL

9.1. Base Beautification Procedures. This chapter establishes policies, assigns responsibilities, and outlines procedures for the maintenance and improvement of grounds at JBMDL. The premise of the base beautification is as follows:

9.1.1. Limited funding and manning dictates that all base organizations take an active role in the base beautification and litter control program.

9.1.2. CE is responsible for the general maintenance of all common area grounds on JB MDL.

9.2. CE Responsibilities. CE administers and manages the grounds maintenance program and ensures that services are provided IAW with Head Quarters Air Mobility Command standards. Specific CE responsibilities are as follows:

9.2.1. Grounds Maintenance Contract. CE oversees the Grounds Maintenance Contractor, who provides a full range of services for the McGuire and Lakehurst campus, as well as the Air Force Expeditionary Center and check point 9.

9.2.2. HQ Facilities and Community Areas. CE provides grounds maintenance service for the landscaped areas (mulch beds or planted areas) at installation level HQ facilities and community areas only. Community areas include but are not limited to; base entry gates, traffic circles, PAX terminal, Child Development Center, Chapels, Fitness Center, Library, Dining Facility, Family Support Center, and Community Activity Center.

9.2.3. Base Appearance Team (BAT). Grounds maintenance efforts on the McGuire area of the installation are augmented by the BAT. CE oversees the BAT of 2-4 military members provided by the base augmentee program. Units assign BAT members to the program on a weekly rotating basis.

9.2.4. Dix Inmate Labor. Dix area of the installation utilizes FCI inmates for grounds maintenance services. CE manages the Inmate Labor Program and work is scheduled on a rotational basis.

Note: Due to intermittent FCI inmate unavailability, there are periods where inmate labor is not able to sustain grass cutting efforts during which time general ground maintenance is accomplished by CE civilians on a priority basis.

9.3. FM Responsibilities. FMs play an active role in maintaining base appearance standards by accomplishing the following functions:

9.3.1. Policing and Litter Removal. FMs are responsible for ensuring that all litter/debris in their areas of responsibility is removed and appropriately discarded. This includes clearing trash, waste, and any debris which might interfere with mower or other maintenance equipment operation or present an unsightly appearance. Occupant responsibility (to include parking lot islands) extends to the halfway point between adjacent facilities, to the natural boundary or, in the absence of both, to a point 50 feet from the facility. Keeping refuse containers policed and all covers closed are inherent in these responsibilities.

9.3.2. Weed Control/Flower Beds Maintenance. FMs are to ensure all landscaped areas surround the facilities with the exception of those identified in 9.2.2 are maintained to a clean, neat, and professional appearance free of weeds and debris. FMs are responsible for the care and up keep of any planted vegetation.

9.3.3. Solid Waste Disposal. FMs are to ensure that refuse is discarded in the appropriate containers. See Chapter 12 for additional guidance.

Chapter 10

ENERGY & WATER CONSERVATION

10.1. General. JBMDL actively maintains a number of diverse military missions, while managing a variety of major energy and water conservation efforts. These efforts aim to meet and surpass usage reduction goals set IAW all applicable Federal, State, and Air Force regulations. To that end, JBMDL relies on the continued cooperation and involvement of its mission partners and tenants. The brief guidelines outlined here assist the FM as the lead for these efforts in understanding their responsibilities for proper energy and water management at their facilities.

10.2. FM Responsibilities. The FM is responsible for ensuring appropriate energy and water management efforts are maintained at assigned facilities. Responsibilities include, but are not limited to:

10.2.1. Promoting a positive attitude for energy management practices.

10.2.2. Ensuring thermostats are set at correct temperatures during heating or cooling season as found in appendix C

10.2.3. Verifying all windows and doors are closed when the building is being heated or cooled.

10.2.4. Turning off all lights when not in use during and after duty hours.

10.2.5. Monitoring outside lights during daylight hours to minimize excess use beyond safety or security reasons.

10.2.6. Minimizing the power drainage from unnecessary and un-required building equipment.

10.2.7. Securing plumbing fixtures to prevent leakage.

10.2.8. Conducting periodic inspections of assigned facilities.

10.2.9. Notifying area specific CE Customer Service sections when discovering energy or water wasteful conditions in facilities that need correction.

10.3. Contacting Energy Management. The Joint Base MDL Energy Management may be reached at the following email address: **87ces.energy@us.af.mil**

Chapter 11

ENVIRONMENTAL GUIDANCE

11.1. General. The FM is responsible for ensuring adequate environmental protection at assigned facilities. This instruction establishes guidelines and assists the FM and base community in recognizing environmental issues and assuring the sustainability of the military missions.

11.2. Environmental Policy. As an installation, JBMDL is committed to improving environmental performance, ensuring environmental compliance, and minimizing pollution. In all activities, JBMDL seeks to be active stewards of our environment and protect its resources. Compliance with environmental laws and this policy is the responsibility of every member of the JBMDL community in accordance with his or her roles and responsibilities within the organization. As an installation, JBMDL will:

11.2.1. Be compliant with all Federal, State, and local environmental laws.

11.2.2. Maintain a current environmental management system.

11.2.3. Establish quantifiable goals for environmental performance.

11.2.4. Conduct routine management reviews to continually assess our progress toward environmental goals and update our operating procedures to stay in line with our goals.

11.2.5. Ensure responsible use of energy through adoption of innovative practices and procedures that will conserve energy and improve efficiency.

11.2.6. Responsibly manage the natural and cultural resources held in public trust.

11.2.7. Recycle natural and manmade materials.

11.2.8. Reduce/eliminate pollution without compromising the mission.

11.2.9. Increase our community's awareness of our environmental policies and progress through press releases, public meetings, adopt-a-school programs, Earth Day activities, and the Internet.

11.3. Environmental Management System. The primary program for communicating environmental requirements is the installation's Environmental Management System (EMS). EMS refers to the management of the environmental programs in a comprehensive, systematic, planned and documented manner. The EMS establishes a management framework by which an organization's impacts on the environment can be systematically identified and reduced. It offers a structured way to incorporate environmental considerations into day-to-day operations and promotes continual improvement of the environment and human health. Environmental compliance requirements are covered by many Federal and State laws and carry serious penalties for violators.

11.4. Spills. Any oil or chemical spill on JBMDL, without any consideration of amount or size, is considered an emergency and therefore is a potential life, health, fire, or other safety hazard. Witnesses to spills should notify the Fire Department immediately. If a spill occurs, the individual discovering the spill will make every effort to take the following actions as soon as possible:

11.4.1. Call 9-1-1.

11.4.2. Stop the flow and/or of the product flow. This includes securing pumps and close valves.

11.4.3. Warn personnel by sounding alarms.

11.4.4. Enforce safety and security measures.

11.4.5. Shut off ignition sources to include motors, electrical sources, and open flames.

11.4.6. Contain the spill by securing valves, blocking drains, and deploying absorbents.

11.4.7. Make notifications via supervisors, the fire department, and environmental personnel.

11.4.8. Begin cleanup for the spill within personal capabilities.

11.5. Recycling. Recycling services are provided throughout the installation. Typical recyclable materials picked up at convenient locations include office paper, newspaper, glass bottles, aluminum cans, and cardboard. FMs can make arrangements for recycling rechargeable batteries, fluorescent light tubes, vehicle batteries, appliances and electronics and obtaining additional recycling containers can be made by contacting 87 CES/CEAN. Alkaline batteries are not hazardous or recyclable and may be disposed of as regular trash. See Chapter 12 for additional guidance.

11.6. Hazardous Waste. The generation, storage and disposal of hazardous waste are highly regulated and carries serious penalties for non-compliance with Federal and State regulations. Compliance inspections by Federal and State regulatory agencies are frequent and often unannounced. FMs should contact 87 CES/CEAN for advice and assistance in identifying hazardous waste and setting up compliant hazardous waste accumulation areas. Disposal of hazardous waste in ordinary trash containers is illegal.

11.7. Pollution Prevention. In order to limit or eliminate costly disposal of unwanted hazardous materials and prevent releases of hazardous materials into the environment, JBMDL utilizes a HAZMART program to control the purchase of hazardous materials. All JBMDL mission partner and tenants are encouraged to participate in this program.

11.8. Air Pollution Control. Air emissions are strictly controlled by air operating permit issued by State regulatory agency. Installation of all equipment with the potential to generate new or additional air pollutants must be reviewed prior to purchase and installation by 87 CES/CEAN. Affected equipment includes water boilers, air furnaces, paint spray booths, dust collectors and emergency generators.

11.9. Storm Water Protection. Storm water discharges are regulated by installation-wide storm water permits. Discharge of any non-storm water material into the storm sewer system is prohibited. Installation operations must utilize best management practices such as secondary containments for hazardous materials and designated vehicle wash facilities to prevent accidental releases into the storm water system.

11.10. Environmental Impact Analysis. All military and civilian personnel assigned to and/or under the operational control of the Installation Mission Partners, tenant organizations, contractors, and all other persons performing duties at any JBMDL military operational and training facilities shall follow the environmental analysis processes established in the National

Environmental Policy Act (NEPA) during the planning phase and prior to construction of any project on JBMDL. The environmental analysis process is a project planning tool that identifies environmental issues early in the planning process and provides alternatives for potential restrictions. It is the responsibility of the FM and project proponent to initiate the environmental analysis process by submitting an AF Form 813, *REQUEST FOR ENVIRONMENTAL IMPACT ANALYSIS*, to 87 CES/CEAN for review and providing for appropriate funding in the project. Failure to include environmental reviews will delay the project.

11.11. Environmental Division Contact Information. For environmental questions, the primary points of contact within the 87 CES/CEAN Environmental Section are as follows:

11.11.1. Chief, JB MDL Environmental, Joe Rhyner, 609-754-6166, or 609-562-2189

11.11.2. EMS Coordinator , Glen Olshefski, 609-562-2218

11.11.3. Compliance Supervisor, Robert Previte, 732-323-7800

11.11.4. Natural/Cultural Resources Supervisor, John Joyce, 732-323-2911

11.11.5. Restoration Supervisor, Curtis Frye, 609-754-4952

Chapter 12

REFUSE AND RECYCLING

12.1. General. FMs are responsible for ensuring that general refuse and recyclable materials generated at their assigned facilities are discarded appropriately and that the established guidelines below are implemented.

12.2. FM Responsibilities. FMs are responsible for accomplishing the following functions:

12.2.1. Ensuring compliance with and utilization of the qualified recycling program as outlined in section 12.4. This includes ensuring that recyclable products generated at assigned facilities are segregated and placed in appropriate recycling containers or brought to a central collection point.

12.2.2. Removing unauthorized material from the facility's assigned refuse or recycling containers

12.2.3. Ensuring items marked for disposal containing more than 50% metal are taken to the recycling center

12.3. Qualified Recycling Plan (QRP). JBMDL has established recycling as a high priority that contributes to overall mission sustainability goals. The JBMDL QRP establishes recycling goals, monitors recyclable collection, measures recycling effectiveness, and collects revenue from the sale of recyclables to maintain the program. The QRP establishes the following general guidelines:

12.3.1. Recyclable materials such as office paper, newspaper, cardboard, metal cans, and glass bottles are to be placed in the designated recyclable containers located at the central collection point within the facility. These containers are emptied periodically by the recycling contractor. If required, additional recycling collection containers can be obtained from 87 CES/CEAN.

NOTE: Food containers should be completely emptied and rinsed prior to placement in recycling bins.

12.3.2. Arrangements can be made with 87 CES/CEAN to pick up or drop off items that contain hazardous materials such fluorescent light tubes, rechargeable batteries, vehicle batteries, and used motor oil.

12.3.3. Bulky items such as household appliances, wood pallets, scrap metal, government tires, and toner cartridges can be dropped off at the installation's Recycling Centers.

12.3.4. Electronic equipment such as computers, cameras, circuit boards, TVs, or similar can be dropped off at **UNICOR Recycling**, Building 5735. The POC for the UNICOR recycling facility is Jeff Eobstel at Phone # 609-723-1100 x1348.

12.4. Recycling Center Locations. The recycling centers for the respective areas of the installation are as follows.

12.4.1. McGuire/Dix: Building 2321

12.4.2. Lakehurst: Building 669

12.5. Refuse/Solid Waste Disposal. FMs are to ensure that facility refuse is discarded only in receptacles identified for this specific purpose. Disposal of recyclable material in general purpose dumpsters is prohibited and may result in interruption of service. Although a normal, periodic trash pickup schedule has been established, FMs can contact their area specific CE customer service desk if additional services are required. Additionally, FMs are to comply with the following general guidelines:

12.5.1. Disposal of hazardous wastes and hazardous materials in refuse dumpsters or recycling containers is strictly prohibited.

12.5.2. Green waste and wood is not to be disposed of in facility refuse containers. These items to be brought to the following designated location and placed in dumpsters unless marked for that specific purpose

12.5.2.1. McGuire/Dix: Recycling Center bldg. 2321 or behind bldg. 3104

12.5.2.2. Lakehurst: Recycling Center bldg. 669

12.5.3. Disposal of construction or demolition waste generated by any contractor without prior written approval by CE is prohibited.

Chapter 13

SELF-HELP PROGRAM

13.1. General. Implementation and completion of a self-help project is a means to improve working conditions and quality of life on this installation. Successful completion of these projects aids in maintaining base facilities at a high-level of repair and use, while at the same time allows CE craftsman the ability, time, and funding to maintain critical assets at a high-level of mission status. Additionally, certain types of work do not require professional expertise and are within the capabilities of the FM or facility occupants. In these instances, the requester has the option of furnishing the labor and/or material funds from their own organization's resources in the base "Self-Help and Minor Maintenance" program.

13.2. Benefits to Organizations. This program is an excellent way to accomplish minor maintenance projects, which would otherwise be classified as a low priority for CE accomplishment. The self-help program offers units/organizations an avenue to accomplish work without expending CE man-hours by utilizing in-house labor resources.

13.3. Self-Help Process. Self-help work must be requested through the AF Form 332 process initiated by the facility manager IAW procedures outlined in chapter 4. This process is the same as for any other work request, with the exception that the donated resources section of the AF Form 332 will be selected. FMs must have an approved 332 prior to the start of any self-help project. Once the AF Form 332 is approved, CE will assign an inspector to the project. The inspector will contact the FM, issue a self-help permit, and provide oversight of the work.

13.3.1. Considerations for Approval. In deciding whether or not to approve the self-help request, CE will consider:

13.3.1.1. Whether the requester has the technical capability and resources available to do the job.

13.3.1.2. What CE support will be required if the requester has limited capability.

13.3.1.3. Whether or not it would be economical for the requester to donate the necessary labor and materials for accomplishment under CE supervision.

13.3.2. CE Responsibilities. Once the self-help project has been approved, CE will provide the following:

13.3.2.1. Provide construction/maintenance expertise and oversight for all self-help work orders and issue approvals prior to start of work.

13.3.2.2. Be the focal point to manage, inspect, and accept all self-help work orders.

13.3.2.3. Provide certain loaner tools to support FM "self-help" requests. Examples of tools for loan are: rakes, wet/dry vacuums, hammers, saws, lawn mowers, shovels, reserved parking signs, levels, leaf blowers, snow blowers, and paint brushes.

13.3.3. FM Responsibilities. FMs are the responsible for the following:

13.3.3.1. FMs must brief personnel assigned to facilities that all self-help projects must be approved on an AF Form 332 and self help permit prior to starting any work, regardless of source of materials

13.3.3.2. Minor Maintenance. FMs will brief facilities occupants that certain minor facility and grounds maintenance actions beyond those under CE contract can be accomplished by means of loaner tools through the self-help program. As FMs are the only individuals who can check out these tools, they will coordinate actions appropriately.

Note: Self-help work not meeting base standards/codes will be required to be resolved at the FM unit's expense. These standards/codes will be explained prior to the start of any work. CE personnel will be available to provide clarification of the base standards/codes.

13.4. Self-Help/Minor Maintenance Examples. The following is a list of typical minor maintenance/facility upkeep tasks which may be authorized for accomplishment via a self-help project. Tools and materials are available for such actions, but can only be checked out by FMs.

Note: Due to regulatory standards, facility occupants are not permitted to accomplish electrical work as "self-help."

13.4.1. Limited painting (5-gallons per year/facility)

13.4.2. Repairing small holes in drywall or spackling

13.4.3. Replacing/repairing floor and ceiling tiles

Minor construction of offices

13.5. Material Support. The Self-Help function is managed by the CE McGuire area material acquisition section in Building 3104. They provide support for materials for minor maintenance efforts and other self-help efforts. Their section can be reached at DSN 650-4170.

Chapter 14

SNOW & ICE REMOVAL PROCEDURES

14.1. Removal of Snow and Ice. FMs play a pivotal role in providing access to their assigned facility during snow and ice storms. It is the responsibility of the FM to ensure ice and snow around entrances and is removed and deicer placed. FMs are required to obtain, distribute, and place deicer on sidewalks, entrance ways, and appropriate areas with the intent of providing access to the facility. Further area specific details are as follows:

14.1.1. McGuire-Dix. FMs can sign out snow removal equipment (shovels/snow blowers) on an as needed per event basis from the McGuire area Self Help store located in Building 3104. Please note that supplies are limited and provided on a first come first serve basis. Additionally, it is important to note that Dix sidewalk snow removal efforts are aided by inmates from the Federal Corrections Institute (FCI). Although these individuals clear and maintain the common use sidewalks they do not clear the sidewalks or an area surrounding individual facilities as this is a unit responsibility. For specific questions on how the inmate labor efforts affect an FM's responsibility area, contact Dix CE customer service.

14.1.2. Lakehurst. FMs can sign out snow removal equipment (shovels only) on an as needed per event basis from Building 272. Note: supplies are limited and provided on a first come first serve basis.

14.1.2.1. NAVAIR Facilities. NAVAIR directly funds snow removal requirements to include sidewalks and entrance ways. FMs for these facilities are not required to perform snow removal and/or placing of deicer.

14.2. Deicer Pick-up. FMs must arrange for the pickup and distribution of their facility's designated allotment of deicer each year from their area specific CE self help store. Locations are as follows:

14.2.1. McGuire/Dix: Building 3104

14.2.2. Lakehurst: Building 272

Chapter 15

MISCELLANEOUS PROVISIONS

15.1. Base Signage. The installation policy regarding sign installation standards is developed from the Unified Facilities Criteria (UFC) 3-120-01, and the installation architectural compatibility plan. Noteworthy features are as follows:

15.1.1. Interior signs must present a uniform and professional appearance.

15.1.1.1. Interior signs will contain condensed and consolidated information to minimize the number of signs by using designated bulletin boards or other central information centers.

15.1.1.2. All exterior signs on JBMDL must be approved by CE on an AF 332 prior to installation. Base signage must adhere to the standards as established by the above UFC. All incompliant signs are incrementally being phased out or replaced.

15.1.1.3. CE Responsibilities. In regards to the base signage program, CE is responsible for the following:

15.1.1.4. Administering and overseeing the JBMDL sign program. This includes establishing the means to acquire, install, and maintain all exterior installation sign requirements

15.1.1.5. Serve as the approval authority for all exterior sign requests

15.1.2. FMs Responsibilities. In regards to the base signage program, FMs are responsible for the following:

15.1.2.1. Acquiring, installing, and maintaining all interior facility signs

15.1.2.2. Identify sign requirements and initiate make requests for signs through area specific CE customer service section. All requests for signs will be submitted on an AF 332 and clearly delineate requirements.

15.1.3. Parking Placards/Reserved parking signs should not exceed 10% of the total parking spaces available at any given facility. Parking spaces must be marked by number or office symbol. When use of office symbol is not applicable use brief description (i.e. Visitor or Customer Service)

15.2. Non-Fair Wear and Tear of Air Force Real Property. FMs in cooperation with facility occupants have the primary responsibility to prevent facility abuse. Non-fair wear and tear of Air Force Real Property will not be tolerated. Non-fair wear and tear can be defined as any willful damage to a facility or any of its components. Any damage should be reported immediately to the CE. Unreported damage to Air Force Real Property clearly indicates that the FM is not conducting periodic inspections.

15.3. Portable Space Heaters. Unrestricted use of portable space heaters is not permitted due to safety, energy conservation, and electrical circuit capacity concerns. Their use directly counters the energy savings CE plans to achieve. CE may grant waivers to accommodate documented and validated special medical circumstances. In cases where a facility's heating

system is going to be inoperative for an extended period of time, FMs may request approval to use space heaters until the heating system is fixed.

15.3.1. Requesting Approval. All requests to utilize portable space heaters must be submitted to the CE via an AF Form 332. CE will ensure all applicable agencies coordinate on the request to address any fire, safety, electrical, and HVAC concerns.

15.3.2. Documentation Required. Individuals with a special medical circumstance must provide documentation from their doctor stating the need for the use of a portable space heater and specifying a temperature range for the individual. The FM will submit the request, along with the documentation from their doctor, for the use of a portable space heater to CE on behalf of the individual/supervisor.

15.3.3. Space Heater Specification Restrictions. All space heaters must be Underwriters Laboratory (UL) listed or Factory Mutual approved. Units must have a built-in tilt switch and a screen over the heating elements. All space heaters must have an electrical rating of 110 or 120 volts with no more than 550 watts electrical heat rating, be kept at least 36 inches away from combustible materials, and will not be left unattended. Do not plug the portable space heater into an extension cord or multi-outlet strip. Safe and proper use of space heaters will be the responsibility of the user and the FM.

15.4. Public Access Defibrillation (PAD) Program. FMs should be aware that various facilities on base are incorporated into the PAD program. The goal of the PAD program is to place Automatic External Defibrillators (AEDs) at appropriate locations on JBMDL. In the event that someone suffers cardiac arrest, these AEDs can be used only by trained personnel prior to the arrival of emergency personnel. The 87th Medical Group is the only organization on JBMDL that can approve placement of an AED. Upon request, the 87th MDG will perform a site assessment to determine if AED placement is warranted in a particular facility. These site assessments should occur prior to purchasing an AED or if there is an unapproved AED in your facility and every two years thereafter. In addition, the AEDs will be inspected initially and annually by the Biomedical Equipment Medical Technicians (BMET) from the 87 MDG. AEDs are purchased and maintained with unit funds. The POCs for the PAD Program are the Chief of Medical Staff at (609) 754-9046 and Education and Training at (609) 754-9784.

JAMES C. HODGES, Col, USAF
Commander, Joint Base McGuire-Dix-Lakehurst

Attachment 1

GLOSSARY OF REFERENCES AND ADDITIONAL INFORMATION

References

AFPAM 32-1125, *Working in the Operations Management Field*, 23 July 2004

AFPAM 32-1004, *Working in the Operations Flight Facility Maintenance*, 1 September 1998

AFMAN 33-363, *Management of Records*, 1 March 2008

AFMAN 32-1084, *Facility Requirements*, 20 April 2012

AFI 32-9005, *Real Property Accountability and Reporting*, 14 August 2008

AFI 32-2001, *The Fire Protection Operations and Prevention Program*, 24 September 2004

AFOSH Standard 91-203, *Air Force Occupational Safety and Health Standard*, 1 July 1998

AFI 32-1021, *Planning and Programming Military Construction (MILCON) Construction Projects,* 24 January 2003

JBMDL Instruction 32-2001, *The Fire Protection Operations and Prevention Program*

Adopted Forms

AF Form 847, Recommendation for Change of Publication

AF Form 332, Base Civil Engineer Work Order

AF Form 55, Employee Safety and Health Record

AF Form 1487, Fire Prevention Visit Report

AF IMT 2427, Lock and Key Control Register

AF IMT 2432, Key Issue Log

AF IMT 1297, Temporary Issue Receipt

DD Form 1569, Incident/Complaint Report

Prescribed Forms

No Prescribed Forms

Abbreviations and Acronyms

AF—Air Force

AFMAN—Air Force Manual

AFOSH—Air Force Occupational Safety and Health Standard

AFRIMS—Air Force Records Information Management System

APF—Appropriated Funds

CE—87 CEG

CEOIP—CE Customer Service

DSW—Direct Scheduled Work

E332—Electronic, web-based system that replaced the manual processing of the hard-copy AF Forms 332.

FCI—Federal Corrections Institute

FB—Facility Utilization Board or Facility Board

FM—Facility Manager

FSD—Fire Safety Deficiency

GPC—Government Purchase Card

IAW—In Accordance With

OPR—Office of Primary Responsibility

PCS—Permanent Change of Station

RAC—Risk Assessment Code

RAFB—Robins Air Force Base

RDS—Records Disposition Schedule

REWG—Real Estate Working Group

RPIE—Real Property Installed Equipment

RWP—Recurring Work Program

SABER—Simplified Acquisition of base Engineering Requirements

UED—Unit Environmental Coordinator

UL—Underwriters Laboratory

WRRB—Work Request Review Board

Attachment 2

SAMPLE FM APPOINTMENT MEMO

A2.1. The responsible commander or civilian leader shall: prepare and send a memo to their area specific CE Customer Service section in order to appoint facility manger.

Figure A2.1. Sample FM Appointment Memo.

DEPARTMENT OF THE AIR FORCE
HEADQUARTERS AIR MOBILITY COMMAND
JOINT BASE MCGUIRE-DIX-LAKEHURST

Date_____

MEMORANDUM FOR 87th CES, Real Property Office

FROM: _____

SUBJECT: Assignment of Primary/Alternate Building Manager – BLDG(s) _____

The following individuals are assigned as primary/alternate building managers:

Primary Name:_____
Duty Phone:_____
Grade/Rank:_____
Office Symbol:_____
Home or Cell Phone:_____
E-mail address:_____

Alternate Name:_____
Duty Phone:_____
Grade/Rank:_____
Office Symbol:_____
Home or Cell Phone:_____
E-mail address:_____

Commander's signature block
_____
_____

CC:
Individuals concerned
87th CES Customer Service

"This document may contain information which must be propected IAW AFI 33-332, 7.3 and DOD Regulation 5400.11; Privacy Act of 1974 (as amended), and it is FOR OFFICIAL USE ONLY (FOUO)."

NOTE: The sample shown above is the minimum required for CE to accept the appointment.

Attachment 3

FM CHECKLIST

Table A3.1. Facility Manager's Walk-Through Checklist.

No.	Item Description	YES	NO
1.	Become familiar with your facility		
2.	Perform monthly walk through inspections of your facility to ensure:		
	a. Fire safety standard are being met.		
	b. Mechanical room cleanliness including basement areas.		
	c. Operational light fixtures, to include exit and emergency lights and exterior lighting (building and parking lot).		
	d. Fire extinguisher locations and operability.		
	e. Set thermostat(s) to proper temperature settings (68 degrees F in winter and 72 degrees F in Summer) if appropriate.		
	f. Energy conservation standards are being met.		
	g. Electrical outlet usage (to include surge protectors for multiple use items) is appropriate.		
	h. Establish a central location for recycle pickup and disposal.		
	i. All efforts are made to unclog commodes, sinks, and other drains prior to contacting CE Customer Service.		
	j. Facility Manager Data Card (see attachment 6) is placed on bulletin board and in appropriate offices.		
	k. AF Form 1219 is reflecting required work and annotated properly		
	l. Self-help work is being accomplished appropriately and to correct standards.		
	m. Check and inspect ceiling tiles for cleanliness, stains, water damage, etc.; replace as required.		
	n. Replace all burnt out light bulbs as required (below 10 feet), discard properly.		
3.	Perform grounds maintenance and policing.		
4.	Coordinate with CE Customer Service to ensure:		
	a. Commanders are kept informed of infrastructure concerns and actively pursue funding for prioritized requests.		
	b. Work requests are being accomplished in minimum time with an explanation for delays, stoppages, material or parts delays, etc.		
	c. Notification is received for FUB Working Group Meetings.		
	d. Approval for systems furniture is received from CE prior to ordering or installation.		
	e. Communication between CE Customer Service and FM is current and accurate for all work accomplished in your facility.		
	f. Quarterly review and removal of unwanted or unnecessary work requests.		

Attachment 4

LOCK AND KEY CONTROL REGISTER

Table A4.1. AF IMT 2427, Lock and Key Control Register used for Key Control.

LOCK AND KEY CONTROL REGISTER					*I certify that locks and keys listed hereon were audited on date indicated.*	
1. SERIAL NUMBER	2. LOCATION	3. DATE INSTALLED	4. KEY STORAGE LOCATION		5. DATE	6 SIGNATURE
			PRIMARY	SPARE		

AF IMT 2427, 19950701, V2 PREVIOUS EDITION IS OBSOLETE.

Attachment 5

KEY ISSUE LOG

Table A5.1. AF IMT 2432 used for Key Issue Log.

KEY ISSUE LOG						
STRUCTURE	OUT			IN		
	TIME	DATE	SIGNATURE	TIME	DATE	SIGNATURE
			1			1
			2			2
			1			1
			2			2
			1			1
			2			2
			1			1
			2			2
			1			1
			2			2
			1			1
			2			2
			1			1
			2			2
			1			1
			2			2
			1			1
			2			2
			1			1
			2			2
			1			1
			2			2
			1			1
			2			2
			1			1
			2			2

AF IMT 2432, 19950801, V2

Attachment 6

TEMPORARY ISSUE RECEIPT

A6.1. AF IMT 1297 used for Temporary Issue Receipt, if needed.

I acknowledge receipt of and responsibility IAW AFI 23-111 for the items described below and will return them by the return date indicated.

ISSUED TO: SIGNATURE	DUTY PHONE	ISSUED BY	
ISSUED TO: NAME, GRADE, ORGN *(Type or print)*	ORGN ACCT NO.	DATE OF ISSUE	RETURN DATE

STOCK NUMBER	DESCRIPTION OF ITEM	U/I	QNTY

AF IMT 1297, 19870701, V4 PREVIOUS EDITION WILL BE USED. TEMPORARY ISSUE RECEIPT

Attachment 7

FACILITY MANAGER DATA CARD

FACILITY MANAGER INFORMATION

PRIMARY FACILITY MANAGER

_____

(NAME AND DUTY PHONE)

ALTERNATE FACILITY MANAGER

_____

(NAME AND DUTY PHONE)

IF YOU HAVE ANY QUESTIONS REGARDING WORK REQUESTS IN YOUR FACILITY, CONTACT ONE OF THE INDIVIDUALS LISTED ABOVE

Attachment 8

SAMPLE FACILITY ABUSE LETTER

DEPARTMENT OF THE AIR FORCE
HEADQUARTERS AIR MOBILITY COMMAND
JOINT BASE MCGUIRE-DIX-LAKEHURST

DATE

MEMORANDUM FOR INSERT PROBLEM ORGANIZATION NAME

FROM: 87 CES

SUBJECT: Report of Possible Non-Fair Wear and Tear of Air Force Real Property Incident

1. On INSERT THE DATE, personnel from the 87 CES were at Building Number INSERT THE BUILDING NUMBER to accomplish maintenance on Work Order INSERT WORK ORDER NUMBER. It is suspected that this work order is a result of malicious damage caused by personnel within your organization.

2. As your organization is the responsible custodian for this facility, I am requesting that your team investigate the incident to determine if liability can be affixed and reimbursement for damages can be made to the 87 CES for the damages sustained.

3. Request your assistance in developing findings by no later than INSERT DATE.

4. If this damage was the result of misconduct and liability has been affixed, I am further requesting your FM submit a work request into the AF Form 332 system, so that we may prepare the required work order to gain reimbursement from the individual(s) concerned. The work request should not be accomplished until your written request is received. Only temporary emergency repairs will be made to safeguard personnel and property.

MATTHEW P. BENIVEGNA, Lt Col, USAF
Commander, 87th Civil Engineer Squadron

Attachment 9

AF FORM 332 (EXAMPLE)

BASE CIVIL ENGINEER WORK REQUEST
(See Reverse for Instructions)

Form Approved
OMB No. 0704-0188

Public reporting burden for this collection of information is estimated to average .3 hours per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden to the Department of Defense, Washington Headquarters Services, Directorate for Information Operations and Reports, 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 22202-4302, and to the Office of Management and Budget, Paperwork Reduction Project 0704-0188, Washington DC 20503. Please DO NOT RETURN your form to either of these addresses. Send your completed form to HQ AFESC/DEMG.

SECTION I - TO BE COMPLETED BY REQUESTER

1. FROM *(Organization)*	2. OFFICE SYMBOL	3. DATE OF REQUEST	4. WORK REQUEST NO. *(For BCE Use)*
Your Organization			LEAVE BLANK

5. NAME AND PHONE NO. OF REQUESTER	6. REQUIRED COMPLETION DATE	7. BUILDING, FACILITY OR STREET ADDRESS WHERE WORK IS TO BE ACCOMPLISHED
Include point of contact and best contact number		BLDG Number (please identify your annex)

8. DESCRIPTION OF WORK TO BE ACCOMPLISHED *(Include Sketch or Plan, when appropriate)*

Clearly describe your requirement. Attach any sketches, floor plans or other documentation to assist CE in understanding and identifying your requested work. Although we welcome your ideas and solutions, please focus on describing your requirement rather than attempting to provide solutions or address other service related concerns. It is extremely important to provide a clear and detailed description of the requirement and scope of your requested work in this section.

9. BRIEF JUSTIFICATION FOR WORK TO BE ACCOMPLISHED *(Not required for maintenance and repair)*

Ensure that you give a detailed justification for the work you are requesting. This will assist in making the approval decision. Focus on the deficiencies impact on your mission. Please include any safety, environmental or fire code violations and/or any other guidance regarding this discrepancy i.e. AFI, TO, Etc. Please provide a copy of any supporting documents.

10. DONATED RESOURCES

Any resources that YOUR unit will be providing. CHECK the box below for any donated resorces. If none leave blank.

	FUNDS		LABOR		MATERIAL		CONTRACT BY REQUESTER		NONE

11. NAME OF REQUESTER	12. GRADE OF REQUESTER	13. SIGNATURE OF REQUESTER *(See Reverse of Form)*
Name and Duty Phone	Rank or Grade	

14. COORDINATION

Bio-Environmental	Fire Dept	Wing Safety		

SECTION II - FOR BASE CIVIL ENGINEER USE

15. WORK ORDER *(Place an "X" in the appropriate box.)*

	IN-SERVICE		SELF-HELP		CONTRACT		SABER

16. DIRECT SCHEDULED WORK *(Place an "X" in the appropriate box.)*

	EMERGENCY		URGENT		ROUTINE		SELF-HELP		M/C

17. SELF-HELP *(Place an "X" in the appropriate box.)*

	BRIEFING REQUIRED		ADEQUATE COORDINATION		INSPECTION REQUIRED

SECTION III - COMPLETE ONLY IF WORK IS TO BE ACCOMPLISHED BY WORK ORDER

18. WORK CLASS	19. PRIORITY	20. ESTIMATED HOURS	21. ESTIMATED FUNDED COST	22. ESTIMATED TOTAL COST

	23. THERE IS NO NEED FOR AN ENVIRONMENTAL ASSESSMENT (AFR 19-2)		24. A WRITTEN ASSESSMENT IS BEING/HAS BEEN PROCESSED		25. APPROVED		26. DISAPPROVED

27. REMARKS

SECTION IV - APPROVING AUTHORITY

28. NAME AND GRADE *(Please Type or Print)*	29. SIGNATURE	30. DATE

AF IMT 332, 19910101, V4 PREVIOUS EDITION IS OBSOLETE. MASTER FILE COPY

Attachment 10

JBMDL SPACE REQUEST FORM (EXAMPLE)

JOINT BASE MCGUIRE-DIX-LAKEHURST REAL ESTATE SPACE REQUEST

PLEASE COMPLETE DATA REQUESTED BELOW AND FORWARD TO THE 87 CES REAL PROPERTY OFFICE. Upon receipt of your request, it will be reviewed and recommendations submitted to the Real Estate Working Group (REWG) for approval. All recommendations of the REWG will be presented to the 87 ABW Facilities Board unless higher headquarters approval is required. If you have any questions please contact 87 CES Real Property Office at (609) 562-4909/3690/3790.

Service: Air Force/Navy/Army/etc _____ Wing/Brigade/Director equiv: _____

Organization Requesting Space :(Do Not Abbreviate)_____

Office Symbol:_____ POC: _____ Phone No: _____

Type Space Requested (Administrative, Maintenance, Storage (Int/Ext), Special Use, etc):

Amount Space Requested: (SF, SY, etc):

Number Personnel to be housed in space requested: _____

Type/Amount of equipment to be housed: _____

Unit Manpower Authorized (PER UMD or EQUIV) Source: _____

	TOTAL	AUTHORIZED	ASSIGNED
OFFICERS:		_____	_____
ENLISTED:		_____	_____
CIVILIANS:		_____	_____

FACILITIES CURRENTLY OCCUPIED:

SITE: M/D/L	BLDG #	#Rooms	SF/SY
_____	_____	_____	_____

Date Desired/Required:_____, Justification/New Mission _____

_____

_____

(Narrative): [EXAMPLE: The Contractor Motor Pool is responsible for providing ground transportation and cargo movements for over 470,000 mobilizing and demobilizing service members and their associated cargo per Fiscal Year. Until Joint Base merger in FY09, US ARMY has allowed contracted vehicle operators to remain at present location. However, the US ARMY Transportation Division is being relocated from its present location--Bldg 5139 to Bldg 5326 where contractors are located.]

X

_____

Signature of Commander

APPENDIX A FM QUICK REFERENCE GUIDE

The 87th Civil Engineer Squadron is dedicated to serving our customers. In an effort to enhance communications with our customers, we have developed this guide to assist you. If we can be of service to you, please contact us.

1. Civil Engineer Customer Service. This should be the first stop in requesting CE support of any kind.

Hours of Operation	Phone	Location
Normal Duty Hours: 0730-1615 M-F	754-87CE	JBMDL
Afterhours, weekends, and holidays		Contact:
(McGuire)……	754-2451	(Fire Department)
(Lakehurst)…….	323-7816	(Fire Department)
(Dix)……	562-6021	(Water Plant)

If you have any questions or concerns regarding customer service, or work order status contact our Customer Service section at *754-87CE.* Facility Managers may receive one-on-one sessions to discuss projects, work requests, and training.

2. For questions regarding any type of service contract, e.g., refuse collection or custodial service; contact our ***Quality Service Areas listed below.***

Item of Interest	*Office Symbol*	*Phone*
Customer Service (JBMDL)	87 CES/CEOSC	754-87CE(23)
Planning (McGuire/Dix)	87 CES/CEOSS	754-6780
Planning (Lakehurst)	87 CES/CEOSS	323-2608
Programs (McGuire/Dix)	87 CES/CEPD	754-8543
Programs (Lakehurst)	87 CES/CEPD	323-2608
Service Contract (McGuire/Dix)	87 CES/CEOSS	754-5481
Service Contract (Lakehurst)	87 CES/CEOSS	323-2860
Digging Permits (McGuire)	87 CES/CEOSC	754-2388
Digging Permits (Dix)	87 CES/CEOSC	754-2388
Digging Permits (Lakehurst)	87 CES/CEOSC	754-2388

3. For questions / problems involving space utilization, contact our **Asset Management Real Property Office at 562-4909/3690** (Dix & McGuire) or 732-323-2712 (Lakehurst). For base or facility drawings, the ***Engineering assistance Office***, ***754-5135,*** is ready with computerized maps and as-built drawings.

4. For information concerning do it yourself projects, the ***Self-Help Center, 754-5483,*** is ready and willing to assist you in obtaining the materials you need to successfully complete your project.

87th Civil Engineer Squadron Quick Telephone List

Section	Office Symbol	Phone
Commander	87 CES/CC	754-2640
Deputy Civil Engineer	87 CES/CD	754-2768
Section Commander	87 CES/CCE	754-2268
Commander Secretary	87 CES/CSS	754-3722
Programs Flight	87 CES/CEP	562-2228
• Program Management	87 CES/CEPM	754-4426
Explosive Ordnance Flight	87 CES/CED	754-2205/5828
Fire Protection Flight	87 CES/CEF	754-2451
• Prevention Services	87 CES/CEFP	754-2451
Housing Management	87 CES/CEAC	754-2264
• Base Housing Management	UC	723-4290
• Unaccompanied Housing	87 CES/CEAC	754-2670/5498
Operations Flight	87 CES/CEO	754-6416
• Production Control	87 CES/CEOSC	754-87CE
• Material Control	87 CES/CEOSM	754-5483
• Snow Control (McGuire)	87 CES/CEOSC	754-2726
• Unit Control Center (McGuire, Dix & Lakehurst)	87 CES/CEOSC	754- 4368/4415
• Snow Control (Dix)	87 CES/CEOSC	562-6021
• Snow Control (Lakehurst)	87 CES/CEOSC	323-2731

Real Property Office (Dix & McGuire) Real Property Office (Lakehurst)	87 CES/CEAC	562-3690 323-2712
Emergency Management Flight	87 CES/CEX	754-3055

APPENDIX B FIRE PREVENTION VISIT REPORT INSTRUCTIONS

A7: Steps for completing the AF Form 1487

- Review hazards/deficiencies noted on page 1, block 9
- Review corrective action required on page 1, block 12
- Correct hazards/deficiencies NLT corrective action required date on page 1, block 4
- Annotate date corrected on page 2; block 19; column B
- Under other comments, annotate how the hazard/deficiency was corrected on page 2; block 19; column D
- Have your unit commander sign on page 2, block 21
- Return completed 1487 to the fire department or email NLT suspense date on page 1, block 5
- You will have 10 days to have corrected action accomplished and the 1487 must be returned by the suspense date that is block 5 of the 1487
- If a hazard/deficiency cannot be corrected by the date required please indicate the work order #, appointment time, or other justifiable reason that the hazard/deficiency cannot be corrected.

Hand carry your 1487 to your functional manager. If you fail to return the 1487 by the suspense date, your unit commander, director or senior reporting official will be issued a 1487 for not complying JBMDL 32-2001.

Functional manager will be unit commander, director or senior reporting official.

The functional manager is not the facility manager.

If you have any questions, please contact the JBMDL fire prevention offices at 754- 3326 562-5484 or 732-323-7878.

APPENDIX C FACILITY HEATING/COOLING POLICY

1. Purpose: This document establishes standards and policy for operation of facility heating and cooling systems on JBMDL. It applies to all administration, shop and supply facilities and shall remain in effect until rescinded. Excepted from this policy are living spaces, health facilities, computer server equipment spaces, or other areas where the installation commander approves specific temperature settings required for mission accomplishment.

2. Summer -Winter Changeover – The following policy applies to facilities that require a manual seasonal changeover between the heating and cooling modes:

Heating Season	The heating mode may not begin until the average outside air temperature drops to 55 degrees F for four consecutive days.
Cooling Season	The cooling mode may not begin until the average outside air temperature reaches 75 degrees F for four consecutive days.

3. Space Temperature Settings:

Heating Season (maximum settings)	Administrative Spaces	Occupied: 69 degrees F Unoccupied: 55 degrees F
	Shop Spaces	Occupied: 65 degrees F Unoccupied: 55 degrees F
	Warehouse Spaces	60 degrees F
Cooling Season (minimum settings)	Administrative Spaces	Occupied: 76 degrees F Unoccupied: 84 degrees F
	Shop Spaces	Occupied: 76 degrees F Unoccupied: 84 degrees F
	Warehouse Spaces	Not cooled unless required for proper storage of perishable materials.

Note: Unoccupied also applies to night and weekend periods when personnel are not normally present. Night setback temperatures should begin at 6 pm local time, and end at 6 am local time allowing sufficient time for building temperatures to reach normal daytime settings by 7 am. Weekend setback should be from 6 pm Friday until 6 am Monday.

4. Use of EMCS: Facilities with an automated control system such as an Energy Management and Control System (EMCS) or Direct Digital Controls (DDC) shall use these systems to their full potential to monitor and control HVAC equipment and the spaces that they serve.